SAVE 35%-45%

ON
VERTICAL MATERIAL MOVEMENT
LABOR
TOWER CRANE
AND
MAN & MATERIAL HOIST RENTAL!

The SUPER HOIST SYSTEM INCLUDES:

- 1 Super Hoist (6,000# Capacity)
- 3 Fully Retractable Decks
- 1 Pipe & Rebar Cart
- 1 Drywall Cart





239-274-LIFT (5438) P.O. Box 62066 Ft. Myers, FL 33906 www.airoind.com mark@airoind.com

Labor Rate used to calculate may change, but percentage of savings remains the same.

Data is from \$1.2 Billion 5 Story University Medical Center Hospital in New Orleans, LA. A Skanska Project

1105pital in 11ch O	u i i oject				
COST PER LIFT	SOVEO HOISTING SYSTEMS	Tower Crane	Rack & Pinion (Man & Material) Hoist	Mast Climber	Scaffold Hoist
Equipment Rental Pro-rated Per Avg. # Loads	\$3.22	\$59.09	\$4.24	\$2.36	\$2.41
Remove from Transport	Ş3.22	\$17.50	\$17.50		
Transport to Compound		\$17.50	\$17.50		
Breakdown of Pallet to Smaller 2 Loads		\$17.50	\$17.50		
Transport of Split Pallets to Load Position			\$17.50	-	
Waiting Time		\$27.50	\$27.50		
Load into Hoist or Climber			\$17.50		-
Tower Crane Time (Process)		\$52.00		\$29.05	\$29.05
Verticle Transit Time	\$1.66	\$3.32	\$3.32	\$4.98	\$4.98
Transport of Pallet to Work Position	\$4.75	\$10.50	\$10.50	\$10.50	\$10.50
TOTAL COST INCLUDING EQUIPMENT RENTAL	\$9.63	\$187.41	\$133.06	\$161.89	\$161.94
TOTAL COST SEPARATE FROM EQUIPMENT RENTAL	\$6.41	\$128.32	\$128.82	\$159.53	\$159.53



LOAD MOVEMENT IN MINUTES	SEVEO HOISTING SYSTEMS	Tower Crane	Rack & Pinion (Man & Material) Hoist	Mast Climber	Scaffold Hoist
Remove from Transport	3	3	3	3	3
Transport to Compound		2	2	2	2
Breakdown of Pallet to Smaller 2 Loads			5	5	5
Transport of Split Pallets to Load Position			6	6	6
Waiting Time		88	10	14	14
Load into Hoist or Climber			3	2	2
Verticle Transit Time	2	4	4	6	6
Transport into building	2	3	3	3	3
Transport of Pallet to Work Position	3	6	6	6	6
MINUTES	10	106	42	47	47



LEASING OR PURCHASE AVAILABLE!